

PT F7 Lintels

Introducing Programmed Timber (PT)
F7 Lintels.

Made using
Solar Power

Sustainable
Forests



Programmed
Timber



PT F7 Lintels

Programmed Timber lintels are sourced from Australian sustainably grown radiata pine and are a versatile and cost-effective solution for the construction of buildings, providing critical support for masonry and other construction materials above openings such as doors, windows, and fireplaces. Programmed Timber Lintels are extremely cost effective in shorter spans, as compared to other engineered products.

Made from high-quality, solid, kiln-dried softwood, our lintels are strong, durable, and easy to install.

1. **Strength:** Our softwood lintels are engineered to meet the span requirements of AS1684, ensuring maximum load-bearing capacity and safety for your building.
2. **Durability:** Our lintels are treated with a preservative to protect against insect attack, ensuring a long service life for your building.
3. **Versatility:** Our lintels are available in a range of standard sizes and custom lengths to meet the specific requirements of your project.
4. **Ease of installation:** Our lintels are designed to be quick and easy to install, reducing construction time and costs.
5. **Cost-effectiveness:** Our softwood lintels are a cost-effective alternative to other materials such as steel, concrete, LVL or glue laminated beams providing a great value for your building budget.

Quality Assurance:

Our softwood lintels are manufactured to the highest standards, using only the best materials and state-of-the-art manufacturing processes. All our lintels are graded to comply with AS2858, ensuring that they meet or exceed all relevant safety and performance requirements.

When you choose our Programmed Timber lintels, you're choosing a product that's engineered for strength, durability, and ease of installation. Whether you're building a new home, re-modelling an existing building, or constructing a commercial property, our lintels are an excellent choice for your project.

Specification

Materials: ■ 100% Australian Radiata Pine timber

Dimensions: ■ 90x45, 140x45, 190x45 and 240x45

Lengths: ■ Available in 1.165m, 1.765m, 2.365m
■ Or can supply lengths as per your requirements.

Treatment: ■ Available in non-treated or H2F

Moisture Content: ■ The moisture content of the Programmed Timber F7 Lintels shall be between 10% and 18% when tested in accordance with Australian Standard AS 1080.1.

Packaging: ■ Packs can be wrapped in plastic for weather protection if required.
■ Each pack will be clearly labelled with the product name, dimensions, treatment, and grade.
■ Pack will be strapped with no less than 2 bearers.

Grading: ■ The F7 Lintels are individually marked to comply with AS 2858.1-2008
■ H2F Lintels will be individually marked to comply with AS1604

Contact us today to learn more about our products and when we are delivering into your area.

Programmed Timber
44 Links Road
St. Marys NSW 2760

Tel 02 9623 7866
contact@ptimbers.com.au
www.ptimbers.com.au

Programmed
Timber 